

Minotour®

From after-school youth groups to senior center outings, a safe, comfortable mode of transportation is non-negotiable. That's why we equipped the compact Minotour with all the peace-of-mind features that come standard in our larger buses, like the one-piece skirt-to-skirt roof bows and the wrap-around bumper. And while safety comes standard in every Minotour, an impressive list of features can be customized to best serve your passengers. Since 1936, Thomas Built has been building safe buses to meet the needs of passengers, drivers and the community. And with one of the most extensive dealer networks in the industry, there's always support nearby when you need it.

SPECIFICATIONS

Passenger capacity

Up to 30

Wheelbase

Ford® Chassis: 138" or 158" GM® Chassis: 139" or 159"

GVWR

SRW 10,100 lbs., DRW 10,050-14,500 lbs.

Engine

GM gas 4.8L V8, 6.0L V8; GM diesel 6.6L V8; Ford gas 5.4L V8, 6.8L V10

Propane option

GM 6.0L LPG, with fully-integrated liquid propane injection system

CNG option

GM 6.0L Vortec powered by IMPCO Automotive



Minotour

SAFETY

- Meets or exceeds FMVSS/CMVSS
- Built like a full-size school bus
- Safety cage body construction with one-piece skirt-to-skirt roof bows
- Two internal roof crash rails for rollover protection
- Daytime running lights
- · Four-wheel anti-lock brakes
- 42" x 47" glass-paneled rear emergency door

DRIVABILITY/COMFORT

- 73" interior headroom
- · Interior dome lights
- Driver-friendly ergonomic instrument panel
- 6" x 16" interior rearview mirror with padded edges
- Thermal poly fiber insulation

DRIVER VISIBILITY

- Driver control panel placed overhead
- Manually-operated front entrance door
- 306 square-inch Saf-T-Vue window

SERVICEABILITY

- Electronics mounted in interior service compartment with light
- Main circuit breaker located inside entrance door as master power to body
- · Access to lights from inside the bus

OPTIONS

- Wheelchair lift with 44" wide door
- Remote control/heated mirrors
- Driver's step
- Electrically-operated front entrance door
- Dash and rear A/C
- Various seat options available: bench seat without belts, with lap belts, with 3-point belts; latch; integrated child seat; or coach-style seating
- Roof hatch
- Third center LED brake light
- Child reminder system
- · Acoustical headlining
- Manual reset electrical circuit breakers
- · Reading lights
- · Overhead book racks
- Exterior graphics



Integrated child seat with seatbelt is one of many seating options.



Center aisle with optional book racks and coachstyle seating.



The Saf-T-Vue window offers 306 square inches of glass for optimal exterior visibility.



Driver switches located overhead for easy access and enhanced loading visibility.



